BRUHAT BANGALORE MAHANAGARA PALIKE
YELHANKA ZONE ELECTRICAL DIVISION

Office of the Executive Engineer
Electrical Division, Yelahanka Zone
Bruhath Bengaluru Mahanagara Palike

Name of Work:-Shifting of DTC No 87 along with LT & HT line in between Median TATA Nagara circle Kodigehalli (Bhadrappa Layout) in O & M 15/1 BESCOM Kodigehalli Ward No 8

Sl. No.	Qty.	Description of Work	Unit	Quoted Rates	
				in Figures	in words
1	3	Supplaying of 11 Mtrs Spun pole	Nos	16000.00	Rupees Sixteen Thousand Only
2	3	Labour Charges For Erection of 11 Mtrs Spun pole	Nos	2500.00	Rupees Two Thousand Five Hundred Only
3	3	a) Base concreating 1:4:8 1000X1000X150 mm	Nos	700.00	Rupees Seven Hundred Only
4	3	b) Pole concreating 1:2:4 1000X1000X2500 mm	Nos	12000.00	Rupees Twelve Thousand Only
5	3	c) Coping 1:2:4 (as per actuals)	Nos	1000.00	Rupees One Thousand Only
6	40	Supplaying of Piercing connector suitable for 16 Sqmm -95 sqmm AB Cable-Service connections	Each	200.00	Rupees Two Hundred Only
7	40	Erection of Piercing connector suitable for 16 Sqmm -95 sqmm AB Cable-Service connections		50.00	Rupees Fifty Only
8	6	Supplaying of Suspension clamp assembly	Each	300.00	Rupees Three Hundred Only
9	6	Erection of Suspension clamp assembly		100.00	Rupees One Hundred Only
10	6	Supplaying of Dead end clamp/Anchor clamp Assy	Per Mtr	130.00	Rupees One Hundred Thirty Only
11	6	Erection of Dead end clamp/Anchor clamp Assy		150.00	Rupees One Hundred Fifty Only
12	6	Supplaying of Universal hooks, Bolts & Nuts	Per Mtr	300.00	Rupees Three Hundred Only
13	6	Erection of Universal hooks, Bolts & Nuts		100.00	Rupees One Hundred Only
14	20	Supplaying of Pre Insulates lugs-CPTAU for 95 sq mm	Per Mtr	330.00	Rupees Three Hundred Thirty Only
15	20	Erection of Pre Insulates lugs-CPTAU for 95 sq mm		150.00	Rupees One Hundred Fifty Only
16	20	Supplaying of End cap for 50/70 sq mm	Per Mtr	20.00	Rupees Twenty Only
17	20	Erection of End cap for 50/70 sq mm		5.00	Rupees Five Only
18	2	Alkathine tube	Per Mtr	500.00	Rupees Five Hundred Only

Sri Lakshmi Varadaraja
Electrical Stores
Proprietor

Executive Engineer
Electrical Division
Yelahanka Zone BBMP
Byatarayanapura, Bangalore-92

19	10	Supplaying and erection of Guy wire 7/10 SWG	Kg	60.00	Rupees Sixty
20	0.06	Supplaying of 11 KV HT Aerial bunch cable 3X95+1X70 Sqmm (Bare/Insulated messenger wire) HT Aerial bunched cable	Kms	630000.00	Rupees Six Lakh(s) Thirty Thousand Only
21	0.06	Stringing of 11 KV HT Aerial bunch cable 3X95+1X70 Sqmm (Bare/Insulated messenger wire) HT Aerial bunched cable	Kms	20000.00	Rupees Twenty Thousand Only
22	2	Supplaying of 11 kv Termination kits	Each	2000.00	Rupees Two Thousand Only
23	2	Labour Charges For 11 kv Termination kits	Each	700.00	Rupees Seven Hundred Only
24	2	Grounding connection for messenger wire	Each	125.00	Rupees One Hundred Twenty Five Only
25	2	Labour For Grounding connection for messenger wire		25.00	Rupees Twenty Five Only
26	3	Anchor sleeves for messengers wire	Each	25.00	Rupees Twenty Five Only
27	3	Labour chargers for Anchor sleeves for messengers wire		5.00	Rupees Five Only
28	2	Supply of Spiral Earth Electrode	Per Mtr	200.00	Rupees Two Hundred Only
29	2	Labour Charges For Spiral Earth Electrode		50.00	Rupees Fifty Only
30	4	Supplaying of 4 Pin Cross arm with pole clamp, bolt & nuts & washers for RCC Pole-GI	Sqcm	300.00	Rupees Three Hundred Only
31	4	Fixing of 4 Pin Cross arm with pole clamp, bolt & nuts & washers for RCC Pole-GI	Nos	100.00	Rupees One Hundred Only
32	4	Supplaying of 2 Pin Cross arm with pole clamp, bolt & nuts & washers for RCC Pole-GI	Mtrs	250.00	Rupees Two Hundred Fifty Only
33	4	Fixing of 2 Pin Cross arm with pole clamp, bolt & nuts & washers for RCC Pole-GI	Nos	100.00	Rupees One Hundred Only
34	20	Supplay and Fixing of 1.1 KV Ceramic Pin Insulator	Nos	40.00	Rupees Forty Only
35	4	11 KV Horizontal X-Arm	Nos	400.00	Rupees Four Hundred Only
36	4	11 KV Horizontal X-Arm	Nos	100.00	Rupees One Hundred Only
37	6	Supplay and Fixing of11 KV Disc Insulator	Nos	300.00	Rupees Three Hundred Only
38	12	Supplay and Fixing of11 KV Pin Insulator	Nos	100.00	Rupees One Hundred Only
39	20	Supplay of PVC Insulation tap	Nos	10.00	Rupees Ten Only
40	10	Supplaying and laying of GI Pipe 100 mm Dia	Mtrs	1150.00	Rupees One Thousand One Hundred Fifty Only

Sri Lakshmi Varadaraja
Electrical Stores
Proprietor

	20	Supplaying and laying of PVC Pipe 150 mm Dia	Mtrs	300.00	Rupees Three Hundred Only
42	10	Supplaying and laying of PVC Pipe 25 mm Dia	Mtrs	30.00	Rupees Thirty Only
43	45	Supplaying and laying of Al.lead wire 240 sq mm	Mtrs	200.00	Rupees Two Hundred Only
44	12	Supplaying of fixing of Copper legs 240 sq mm	Nos	200.00	Rupees Two Hundred Only
45	4	Supplaying of fixing of PG Clamp-Rabbit to 240 sq mm	Nos	300.00	Rupees Three Hundred Only
46	8	Supplaying of fixing of Spacer for DTC wiring	Nos	30.00	Rupees Thirty Only
47	2	Supplaying of fixing of Fish plate with necessary bolts & nuts	Nos	100.00	Rupees One Hundred Only
48	2	Supplaying of fixing of Anti climbing device	Nos	75.00	Rupees Seventy Five Only
49	1	Supplaying of fixing of 11 KV special 3 pin X Arm-GI	Nos	500.00	Rupees Five Hundred Only
50	3	Earthing materials pipe type for grounding	Nos	1500.00	Rupees One Thousand Five Hundred Only
51	15	Releasing and Reerection of RCC Pole - 9 Mtr Long 145 Kg WL X 1.9	No	2500.00	Rupees Two Thousand Five Hundred Only
52	15	Releasing and Reerection of 4 Pin Cross Arm with pole clamp bolt & nuts & washers for RCC Pole -GI	No	150.00	Rupees One Hundred Fifty Only
53	15	Releasing and Reerection of 2 Pin Cross Arm with pole clamp bolt & nuts & Washers for RCC Pole-GI	No	150.00	Rupees One Hundred Fifty Only
54	15	Releasing and Reerection of 11 KV Horizontal X-Arm	Set	150.00	Rupees One Hundred Fifty Only
55	2	Releasing and Reerection of 11 mtrs spun pole	Nos	5000.00	Rupees Five Thousand Only
56	1	Releasing and Reerection of 11 KV/433V, 250 KVA, 3Phase 50 Cys, Distribution transformer Oil type	No	3000.00	Rupees Three Thousand Only
57	1	Construction plat form for DTC	No	25000.00	Rupees Twenty Five Thousand Only
58	3	Releasing and Restringing of Rabbit ACSR Conductor	Kms	5000.00	Rupees Five Thousand Only
59	1.8	Releasing and Restringing ofCoyote ACSR Conductor	Kms	9000.00	Rupees Nine Thousand Only
60	1	Releasing and Reerection of Transformer Structure Kit	Set	4000.00	Rupees Four Thousand Only
61	1	Releasing and Reerection of 11 KV 200 A Single break GOS	No	1500.00	Rupees One Thousand Five Hundred Only

Sri Lakshmi Varadaraja
Electrical Stores
Proprietor

Executive Engineer
Electrical Division
Yelahanka Zone BBMP
Byatarayanapura, Bangalore-92